ADDENDUM NO. 2

TO: ALL PLAN HOLDERS

RE: Downtown Sidewalk Improvements – City of Dekalb, Texas

ADDENDUM DATE: July 17, 2024

The Plans, Specifications and Contract Documents for the above referenced project are hereby modified as follows:

• Project Specifications: Replace TXDOT Item 500-Mobilization with Attached Mobilization specification.

PROJECT CLARIFICATION

1. Dekalb City Hall has recently moved. Address in bid forms should take you to the correct location when typed in Google or Apple maps, but for clarity the Image below shows the location of the current city hall.



ADDENDUM NO.2 ISSUED BY:

A.L. FRANKS ENGINEERING

Multor

Caleb Mudford, P.E. Project Manager



7-17-24

SECTION 1-MOBILIZATION

 <u>DESCRIPTION</u>: This item shall consist of preparatory work and operations, including, but not limited to, those necessary for the movement of personnel, equipment, supplies, and incidentals to the project site; for the establishment of the Contractor's offices, buildings, and other facilities necessary to undertake the work on the project.

This item shall also include other work and operations that must be performed, or for expenses incurred, before beginning work on the various Contract items on the project site. It shall also include pre—construction costs which are necessary direct costs to the project and are of general nature rather than directly attributable to other pay items under the Contract.

2. <u>MEASUREMENT AND PAYMENT</u>: Mobilization will be measured as a complete unit price and will be paid for at the contract lump sum price bid. In computing the allowable partial payments from the schedule below, the percentage of the original Contract earned will be based on all items exclusive of the item Mobilization and any materials estimates part. Payment for Mobilization at any of the listed stages of completion will be made on the basis of percentage of item allowed less all payments made.

PARTIAL PAYMENT S	HECKLE
Percentage of Origina!	//Percentage of Bid Price
Contract Amount Earned	for Mobilization Allowed
*First Progress Estimate	25
*10	50
*25	100

This item will be paid for on regular estimates. Payments on percentages of the original Contract amount other than those set out above will not be considered. No adjustment in the amount bid for this items will be made for additional quantities or items of work required to satisfactorily complete the Contract.

IN NO CASE SHALL THE AMOUNT BID FOR THE ITEM OF "MOBILIZATION" EXCEED 5% OF THE TOTAL CONTRACT AMOUNT FOR ALL OTHER ITEMS LISTED IN THE PROPOSAL. Should the amount entered in the Proposal for this items exceed 5%, the Engineer will reduce it to the maximum allowed amount to determine the correct total bid.

Nothing herein shall be construed to limit or preclude partial payments otherwise provided for by the Contract.

Payment will be made under: **Pay Item** Mobilization

Pay Unit Lump Sum