

KEO ARKANSAS
KEO PARK WALKING TRAIL

BID PROPOSAL

ITEM	QTY	UNIT	DESCRIPTION	TOTAL PRICE
1	1	L.S.	Mobilization including preparatory work and operations including but not limited to, movement of personnel, equipment, supplies, and incidentals to the project site. The lump sum price of _____	\$ _____

2	4	EA	Perform removal of existing _____, coordinating w/city for street closures, and _____ holes with compacted _____, _____, and _____ removals to avoid _____.	\$ _____
			_____ Dollars and _____ Cents/EA	\$ _____

BID PROPOSAL CONTINUED

ITEM	QTY	UNIT	DESCRIPTION	TOTAL PRICE
3	0.12	AC	Perform tree removal and clearing and grubbing required for the installation of proposed walking trail and associated appurtances for the unit price of	\$ _____

4	378	S.Y.	Install 6' concrete sidewalk, incl preparation, sawcutting concrete materials, labor and equipment plans and specification	\$ _____
			_____ Dollars and	\$ _____
			_____ Cents/S.Y.	

BID PROPOSAL CONTINUED

ITEM	QTY	UNIT	DESCRIPTION	TOTAL PRICE
5	65	S.Y.	Install bench area concrete, including,grading, subgrade preparation, materials, labor and equipment as necessary per the plans and specifications for the unit price of	\$ _____

6	6	EA	Furnish all materials, equipment and labor necessary for the installation of Commercial 6' Outlets approved equal	\$ _____ \$ _____

Dollars and
Cents/EA

BID PROPOSAL CONTINUED

ITEM	QTY	UNIT	DESCRIPTION	TOTAL PRICE
7	1	LS	Furnish all materials, equipment, supplies and labor necessary for the installation of van accessible handicap parking space including sign, pavement markings, access aisle striping and all associated appurtenances for the lump sum price of _____ _____	\$ _____
8	36	L.F.	Furnish all materials, equipment, supplies and labor necessary for the installation of _____ for the unit price of _____ _____ Dollars and Cents/L.F.	\$ _____ \$ _____

P-5

BID PROPOSAL CONTINUED

ITEM	QTY	UNIT	DESCRIPTION	TOTAL PRICE
9	60	L.F.	Furnish all materials, equipment, supplies and labor necessary for the installation of 12" HDPE stormdrain for the unit price of _____ Dollars _____ Cents/L.S.	\$ _____
10	1	L.S.	Furnish all materials, equipment necessary to install compacted embankment including all compacting and finish grading for the _____ Dollars and _____ Cents/L.S.	\$ _____

P-6

BID PROPOSAL CONTINUED

ITEM	QTY	UNIT	DESCRIPTION	TOTAL PRICE
11	1	L.S.	Furnish all materials, equipment, supplies and labor necessary tfor the unclassified excavation including all preparation and finish grading for the lump sum price of	\$ _____

12	1	L.S.	Intall & maintain erosion contr in the plans and specificati seeding and other contr to limit erosion control th establish a minimum _____ station	\$ _____
			_____ Dollars and	\$ _____
			_____ Cents/L.S	
TOTAL BASE BID ITEMS (1-12)				\$ _____

BID PROPOSAL CONTINUED

NOTES: Contractor shall submit bids and hold price for a period of no more than 60 days from the opening. All work shall be done in accordance with ADEQ requirements and permits as provided in the specifications.

Unit prices and total prices must be specified in both words and figures, e.g., \$100.00 per hour, Dollars and No Cents. In case of a discrepancy, the amount in words will govern.

Items that are subsidiary to performing the work shall include all labor, materials, and equipment. All materials shall be supplied by the contractor. Existing utilities, trees and improvements shall be protected. The contractor shall coordinate with City of Keo for existing utilities encountered. Protection of existing utilities shall be approved by the engineer prior to construction.

Haul routes approved designated by the city shall be restored to original condition upon completion of the work. This area is not included in seeding / revegetation and shall be maintained for the duration of the work.

Owner reserves the right to select either Base Bid or Alternative Bids and will notify contractor at the time of awarding the contract.

Time required to complete base bid work shall be 90 calendar days. Bidder further agrees to pay as liquidated damages, the sum of \$500 per calendar day thereafter.

BID PROPOSAL CONTINUED

DEDUCTIVE ALTERNATE #1

ITEM	QTY	UNIT	DESCRIPTION	TOTAL
1	33	S.Y.	Item #5: REDUCE Install bench area concrete, including,grading, subgrade preparation, materials, labor and equipment as necessary per the plans and specifications for the unit price of _____ _____	\$ _____
1	2	EA	Item #6: REDUCE Furnish all materials, supplies and labor necessary for the installation of Courtyard Commercial 6" thick concrete slab, approved equal for the above. _____ _____ Dollars and Cents/EA	\$ _____ \$ _____
TOTAL OF DEDUCTIVE ALT. #1				\$ _____
TOTAL BASE BID LESS DEDUCTIVE ALT. #1				\$ _____