

ADDENDUM NO. 1

TO: ALL PLAN HOLDERS

RE: Lake Columbia Spillway Repair-Columbia County, Arkansas

ADDENDUM DATE: August 13, 2026

BID DATE: August 18, 2026

The Plans, Specifications and Contract Documents for the above referenced project are hereby modified as follows:


Bid Proposal Revision: Remove Bid Proposal pages P1 to P-4 and Replace with the attached Bid Proposal pages P1 to P-4.

Clarifications:

1. Removal of unsound or loose material may be accomplished by compressed air or high pressure hydro cleaning
2. Shotcrete provided by a local ready mix plant (5000psi minimum) will be allowed for use.
3. Reinforcing steel is not required for washouts less than 12" in depth.
4. The lake water level will be lowered approximately 6" from its current (August 12, 2026) level prior to construction.
5. The condition and weight limit of the existing steel culvert at the low water crossing is unknown. The successful contractor is to make necessary accommodations to protect all existing structures from construction related damage.
6. Broken soil cement removed from the washout areas can be left on site on the lake side of the levee.
7. Payment for shotcrete in place will be based on truck load volumes.

ADDENDUM NO. 1 ISSUED BY:

A.L. FRANKS ENGINEERING



Anthony L. (Andy) Franks, P.E.
Project Manager

ARKANSAS CERTIFICATE OF AUTHORIZATION NUMBER 1681

OKLAHOMA CERTIFICATE OF AUTHORIZATION NUMBER 5503

TEXAS CERTIFICATE OF REGISTRATION NUMBER F-10338



COLUMBIA COUNTY, ARKANSAS
LAKE COLUMBIA SPILLWAY REHABILITATION

BID PROPOSAL

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
1	1	L.S.	Mobilization including preparatory work and operations, including but not limited to, movement of personnel, equipment, supplies, and incidentals to the project site for the lump sum price of	\$ _____	\$ _____
			_____ Dollars and _____ Cents/L.S.		
2	1320	C.Y.	Provide and Install shotcrete concrete with required re-bar per plans and specifications for the unit price of	\$ _____	\$ _____
			_____ Dollars and _____ Cents/C.Y.		
TOTAL BASE BID ITEMS				\$ _____	

BID PROPOSAL CONTINUED

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
DEDUCTIVE ALTERNATE #1					
1	421	C.Y.	DELETE from station 36+75 to 46+75: Provide and Install shotcrete concrete with required re-bar per plans and specifications for the unit price of	\$ _____	\$ _____
_____ Dollars and _____ Cents/C.Y.				=====	
TOTAL BASE LESS DEDUCTIVE ALTERNATE #1				\$ _____	
DEDUCTIVE ALTERNATE #2					
1	421	C.Y.	DELETE from station 26+75 to 36+75: Provide and Install shotcrete concrete with required re-bar per plans and specifications for the unit price of	\$ _____	\$ _____
_____ Dollars and _____ Cents/C.Y.				=====	
TOTAL BASE LESS DEDUCTIVE ALTERNATE #1 AND #2				\$ _____	

BID PROPOSAL CONTINUED

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
			DEDUCTIVE ALTERNATE #3		
1	242	C.Y.	DELETE from station 21+00 to 26+75: Provide and Install shotcrete concrete with required re-bar per plans and specifications for the unit price of	\$ _____	\$ _____
			_____ Dollars and _____ Cents/C.Y.	=====	
			TOTAL BASE LESS DEDUCTIVE ALTERNATE #1, #2, and #3	\$ _____	