

CITY OF TEXARKANA, ARKANSAS

DRAINAGE IMPROVEMENTS

BID PROPOSAL A – BOBBY FERGUSON PARK (OPTIONAL)

<u>ITEM</u>	<u>QTY/UNIT</u>	<u>DESCRIPTION</u>	<u>TOTAL PRICE</u>
1.	1 LS	Mobilization and Site Preparation for the project including but not limited to: mobilization of equipment necessary, traffic control, and other items required to complete the project. Payment shall be 10% of the total project cost, with the balance >5% prorated over remaining pay items. Accordance with plans and specifications. Price of _____	\$ _____
2.	50 CY.	Furnish and Install 12" concrete pipe with all voids under existing concrete. Payment shall include all materials, labor, and equipment, and shall be in accordance with the plans and specifications. Price of _____ Dollars and _____ Cents/CY.	\$ _____

BID PROPOSAL
(Cont'd)

<u>ITEM</u>	<u>QTY/UNIT</u>	<u>DESCRIPTION</u>	<u>TOTAL PRICE</u>
3.	65 S.F.	Install Concrete Wall Extension (8" thk) to existing weir include dowels, reinforcements, formwork, materials and equipment necessary to perform the work in a with the plans and specifications for the unit price _____ Dollars and _____ Cents/S.F.	\$ _____
4.	20 L.F.	Install Concrete toewall at d/s (_____ ft deep) To include dowels, reinforcement, formwork, labor, and equipment necessary to perform the work in accordance with the plans and specifications for the unit price _____ Dollars and _____ Cents/L.F.	\$ _____
5.	65 SY.	Install _____ geotextile fabric, labor, necessary per the unit price of _____ Dollars and _____ Cents/SY	\$ _____

BID PROPOSAL
(Cont'd)

TOTAL BASE BID PROPOSAL _____

- NOTES:**
- 1) Owner will review and make award based on available budget of Bid P
 - 2) Miscellaneous items, directed work, connections, etc., not specifically listed shall be included to complete the proposed improvements to a complete and operational system shall be included in the most appropriate Bid Item.
 - 3) Time required to complete base bid work shall be 45 calendar days.
 - 4) Contractor shall dispose of demolition items in accordance with local, state and federal regulations.

CITY OF TEXARKANA, ARKANSAS

DRAINAGE IMPROVEMENTS

BID PROPOSAL B – COUNTY AVENUE DETENTION BASIN (STRUCTURE)

<u>ITEM</u>	<u>QTY/UNIT</u>	<u>DESCRIPTION</u>	<u>TOTAL PRICE</u>
6.	1 LS	Mobilization and Site Preparation for the project including mobilizing equipment necessary for the work and cleaning of the interior of the tank for the work. Removing of grit, sludge, debris, etc. as requested, >5% prorated over remaining project in accordance with plans and specifications. Unit price of _____ Dollars. \$ _____ \$ _____	
7.	200 CY.	Provide and install concrete detention basin including excavation, Clay fill embankment, etc. including labor, materials, And equipment in accordance with the plans. Unit price of _____ Dollars and _____ Cents/CY. \$ _____ \$ _____	

BID PROPOSAL
(Cont'd)

<u>ITEM</u>	<u>QTY/UNIT</u>	<u>DESCRIPTION</u>	<u>TOTAL PRICE</u>
8.	100 C.Y.	Furnish and Install flowable fill cement mix to fill voids in existing concrete structure to include pumping, equipment, labor, and materials necessary in accordance with the plans and specifications for the unit price of _____	\$ _____
9.	206 L.F.	Install Concrete toewall at d/s of _____ (see sheet _____) To include dowels, reinforcement, equipment, labor, and equipment necessary in accordance with the plans and specifications for the unit price of _____	\$ _____
		_____ Dollars and _____ Cents/L.F.	\$ _____
10.	100 SY.	Install _____ protection including _____, _____, _____ necessary per _____ for the unit price of _____	\$ _____
		_____ Dollars and _____ Cents/S.Y.	\$ _____

BID PROPOSAL
(Cont'd)

TOTAL BASE BID PROPOSAL B

TOTAL BASE BID PROPOSAL

- NOTES:**
- 1) Owner will review and make award based on available budget.
 - 2) Miscellaneous items, directed work, connections, etc., not included in the bid items shall be added to complete the proposed improvements to a complete and operational system shall be considered under the most appropriate Bid Item.
 - 3) Time required to complete base bid work shall be based on the time required to complete both proposal **A & B** are accepted.
 - 4) Contractor shall dispose of demolition items in a timely manner.